

水道用硬質塩化ビニルライニング鋼管 SGP - VA (ねじ)

管端防食継手

配管工 18,000 円

施工区分	口径	複合単価	価格 円/本	単価 円/m	管		継手		接合材等		支持金物		配管工		はつり補修		その他		計	備考
					補給率	金額	比率	金額	比率	金額	比率	金額	労務歩掛	労務費	比率	金額	比率	金額		
屋内一般	15	2,890	1,590	397	1.10	436	0.60	238	0.05	19	0.10	39	0.089	1,602	0.08	128	0.25	432	2,894	
	20	3,230	1,750	437	1.10	480	0.60	262	0.05	21	0.10	43	0.100	1,800	0.08	144	0.25	486	3,236	
	25	4,110	2,450	612	1.10	673	0.60	367	0.05	30	0.10	61	0.123	2,214	0.08	177	0.25	597	4,119	
	32	5,180	3,290	822	1.10	904	0.60	493	0.05	41	0.10	82	0.151	2,718	0.08	217	0.25	733	5,188	
	40	5,790	3,800	950	1.10	1,045	0.60	570	0.05	47	0.10	95	0.166	2,988	0.08	239	0.25	806	5,790	
	50	7,440	5,170	1,292	1.10	1,421	0.60	775	0.05	64	0.10	129	0.208	3,744	0.08	299	0.25	1,010	7,442	
	65	9,950	7,280	1,820	1.10	2,002	0.60	1,092	0.05	91	0.10	182	0.271	4,878	0.08	390	0.25	1,317	9,952	
	80	11,410	8,550	2,137	1.10	2,350	0.60	1,282	0.05	106	0.10	213	0.307	5,526	0.08	442	0.25	1,492	11,411	
	100	15,050	11,800	2,950	1.05	3,097	0.60	1,770	0.05	147	0.10	295	0.401	7,218	0.08	577	0.25	1,948	15,052	
	125	18,040	14,500	3,625	1.05	3,806	0.60	2,175	0.05	181	0.10	362	0.474	8,532	0.08	682	0.25	2,303	18,041	
	150	22,920	19,800	4,950	1.05	5,197	0.60	2,970	0.05	247	0.10	495	0.577	10,386	0.08	830	0.25	2,804	22,929	
機械室便所	15	3,450	1,590	397	1.10	436	0.90	357	0.05	19	0.10	39	0.107	1,926	0.08	154	0.25	520	3,451	
	20	3,850	1,750	437	1.10	480	0.90	393	0.05	21	0.10	43	0.120	2,160	0.08	172	0.25	583	3,852	
	25	4,910	2,450	612	1.10	673	0.90	550	0.05	30	0.10	61	0.148	2,664	0.08	213	0.25	719	4,910	
	32	6,160	3,290	822	1.10	904	0.90	739	0.05	41	0.10	82	0.181	3,258	0.08	260	0.25	879	6,163	
	40	6,870	3,800	950	1.10	1,045	0.90	855	0.05	47	0.10	95	0.199	3,582	0.08	286	0.25	967	6,877	
	50	8,850	5,170	1,292	1.10	1,421	0.90	1,162	0.05	64	0.10	129	0.250	4,500	0.08	360	0.25	1,215	8,851	
	65	11,810	7,280	1,820	1.10	2,002	0.90	1,638	0.05	91	0.10	182	0.325	5,850	0.08	468	0.25	1,579	11,810	
	80	13,530	8,550	2,137	1.10	2,350	0.90	1,923	0.05	106	0.10	213	0.368	6,624	0.08	529	0.25	1,788	13,533	
	100	17,880	11,800	2,950	1.05	3,097	0.90	2,655	0.05	147	0.10	295	0.481	8,658	0.08	692	0.25	2,337	17,881	
	125	21,430	14,500	3,625	1.05	3,806	0.90	3,262	0.05	181	0.10	362	0.569	10,242	0.08	819	0.25	2,765	21,437	
	150	27,200	19,800	4,950	1.05	5,197	0.90	4,455	0.05	247	0.10	495	0.692	12,456	0.08	996	0.25	3,363	27,209	
屋外配管	15	2,450	1,590	397	1.05	416	0.45	178	0.05	19	0.10	39	0.080	1,440			0.25	360	2,452	
	20	2,740	1,750	437	1.05	458	0.45	196	0.05	21	0.10	43	0.090	1,620			0.25	405	2,743	
	25	3,500	2,450	612	1.05	642	0.45	275	0.05	30	0.10	61	0.111	1,998			0.25	499	3,505	
	32	4,410	3,290	822	1.05	863	0.45	369	0.05	41	0.10	82	0.136	2,448			0.25	612	4,415	
	40	4,910	3,800	950	1.05	997	0.45	427	0.05	47	0.10	95	0.149	2,682			0.25	670	4,918	
	50	6,330	5,170	1,292	1.05	1,356	0.45	581	0.05	64	0.10	129	0.187	3,366			0.25	841	6,337	
	65	8,490	7,280	1,820	1.05	1,911	0.45	819	0.05	91	0.10	182	0.244	4,392			0.25	1,098	8,493	
	80	9,730	8,550	2,137	1.05	2,243	0.45	961	0.05	106	0.10	213	0.276	4,968			0.25	1,242	9,733	
	100	12,980	11,800	2,950	1.05	3,097	0.45	1,327	0.05	147	0.10	295	0.361	6,498			0.25	1,624	12,988	
	125	15,580	14,500	3,625	1.05	3,806	0.45	1,631	0.05	181	0.10	362	0.427	7,686			0.25	1,921	15,587	
	150	19,840	19,800	4,950	1.05	5,197	0.45	2,227	0.05	247	0.10	495	0.519	9,342			0.25	2,335	19,843	
地中配管	15	1,960	1,590	397	1.05	416	0.35	138	0.05	19			0.062	1,116			0.25	279	1,968	
	20	2,200	1,750	437	1.05	458	0.35	152	0.05	21			0.070	1,260			0.25	315	2,206	
	25	2,820	2,450	612	1.05	642	0.35	214	0.05	30			0.086	1,548			0.25	387	2,821	
	32	3,570	3,290	822	1.05	863	0.35	287	0.05	41			0.106	1,908			0.25	477	3,576	
	40	3,980	3,800	950	1.05	997	0.35	332	0.05	47			0.116	2,088			0.25	522	3,986	
	50	5,150	5,170	1,292	1.05	1,356	0.35	452	0.05	64			0.146	2,628			0.25	657	5,157	
	65	6,910	7,280	1,820	1.05	1,911	0.35	637	0.05	91			0.190	3,420			0.25	855	6,914	
	80	7,930	8,550	2,137	1.05	2,243	0.35	747	0.05	106			0.215	3,870			0.25	967	7,933	
	100	10,590	11,800	2,950	1.05	3,097	0.35	1,032	0.05	147			0.281	5,058			0.25	1,264	10,598	
	125	12,720	14,500	3,625	1.05	3,806	0.35	1,268	0.05	181			0.332	5,976			0.25	1,494	12,725	
	150	16,260	19,800	4,950	1.05	5,197	0.35	1,732	0.05	247			0.404	7,272			0.25	1,818	16,266	